	Description	Unit	Approved Tender Rates of BRAHMANANDA REDDY ( )		
			In Figures		In Words
61.25	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	189.78	30602.03	Rupees One Hundred Eighty Nine and Seventy Eight Paise Only
105.22	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200mm etc complete as per specifications and directions of engineer in charge of the work	Sqm	2510.31	264134.82	Rupees Two Thousand Five Hundred Ten and Thirty One Paise Only
23.93	Sand Filling in Foundation Trenches as per Drawing & Technical etc complete as per specifications and directions of engineer in charge of the work	Cum	2642.58	63236.94	Rupees Two Thousand Six Hundred Forty Two and Fifty Eight Paise Only
1400	Fabricating, supplying & erecting M.S. angular Truss of span upto 10m The bottom & top member is provided with 50x50x6mm double equal angles, welded back to back and in between top & bottom line, in areas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided. All the members are welded together with 6mm gusset plate as per Drawing No CBS/ SD/K-Mantap/9/MND/97. The entire truss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc complete as per specifications and directions of engineer in charge of the work	Kgs	112.14	156996.00	Rupees One Hundred Twelve and Fourteen Paise Only
81	Providing, fabricating and fixing profiled poly erethane insulated roof of 1,06m width and 7,60m length sheets roof having external sheet of 0.5mm steel with powder coated finish, bottom sheet of 0.4mm steel with powder coated finish. The roofing system shall have water proof over lapping arrangement at the inter section of two sheets the fasting shall be of self tapping screws dia 6.3mm or required length with PVC head along with washer pre-painted aluminium cap unit with build in seal arrangements. The entire roof shall be firmly fasteed to the existing frame etc complete as per specifications and directions of engineer in charge of the work	Sqm	2156.62	174686.22	Rupees Two Thousand One Hundred Fifty Six and Sixty Two Paise Only
				886982.83	

C. Brahmanandha Reddy

Signature of the Contractor

01/10

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

1/10

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37143

APPROVED SCHEDULE - B

BBMP/E-PMT/11/2019-20, Date: 11.07.2019

...ction of Auditirum at Singapura Paradise in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub ...on.

	Approved Qty.	Description	Unit	Approved Tender Rates of BRAHMANANDA REDDY ( )		
				In Figures		In Words
	33.44	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	172.74	5776.43	Rupees One Hundred Seventy Two and Seventy Four Paise Only
2	4.65	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4665.02	21692.34	Rupees Four Thousand Six Hundred Sixty Five and Two Paise Only
3	7.92	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4013.24	31784.86	Rupees Four Thousand Thirteen and Twenty Four Paise Only
4	4.46	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4797.29	21395.91	Rupees Four Thousand Seven Hundred Ninety Seven and Twenty Nine Paise Only
5	0.99	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5215.2	5163.05	Rupees Five Thousand Two Hundred Fifteen and Twenty Paise Only
6	26.4	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	93.93	2479.75	Rupees Ninety Three and Ninety Three Paise Only
7	6.91	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) etc complete as per specifications and directions of engineer in charge of the work	Cum	5635.02	38937.99	Rupees Five Thousand Six Hundred Thirty Five and Two Paise Only
8	80.63	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	869.36	70096.50	Rupees Eight Hundred Sixty Nine and Thirty Six Paise Only